



Town of Concord

## Concord Middle School

Middle School Building Committee 10.07.2021





### **Project Goals Recap**



Total Project Cost Range per RFS \$80-\$100 M

Total Project Cost maximum currently estimated <\$102 M





Replace two middle schools with one combined middle school, grades 6-8



Design enrollment 700 Students



Team Teaching Model, meet Ed Plan



Design for Net Zero Energy

### **Primary Goal:**

Consolidate two middle school populations into a single, 21st century learning facility that will serve the community for generations.

# Schematic Design





### Schematic Design Estimating Submission

### Three Major Components

#### **Drawings**

- Site (Civil, Landscape Architecture)
- Architecture incl. roof plan with conceptual mechanical equipment locations
- Electrical One-Line Diagram
- NO structural, mechanical, electrical or plumbing drawings

#### **Uniformat Specifications**

- Every discipline provides information
- Contains summary with phasing requirements, information on materials, fixtures and equipment information

#### Report


- Narratives from all design team members
- Sustainability narrative
- Education Plan with design response narratives added
- Additional project imagery
- Site Investigations Reports (if new or updated since Feasibility Study)





#### **Updated Floor Plans**

- Colored plans represent educational use and programming
- Drawing set includes technical drawings with annotations

Note: The Auditorium has been rotated after a preliminary acoustical review was performed by our consultant. More detailed work on auditorium design will be performed at the start of Design Development.







Classroom
Team Commons
Special Education
Vocation/Tech Classroom
Administration
Guidance
Nurse
Media Center
Auditorium
Music
Art
Physical Education
Cafeteria

#### **UPPER-LEVEL PLAN**







EWING SMMA



**TEAM COMMONS** 

10

### **Building Engineering Systems**

#### Mechanical

#### Heating and Cooling

- VRF fan coil units for classrooms, media center, administration and related support spaces and common areas.
- AHUs dedicated to each of the large volume spaces, including the Gym, Cafeteria and Auditorium.
- AHUs to be supported by VRF ACCUs for improved efficiency.
- Auditorium to be served by displacement ventilation.

#### Ventilation

- DOAS heat pump units to provide conditioned ventilation to classrooms, media center, administration and related support spaces and common areas.
- Ventilation distribution to spaces controlled by VAV boxes based on space CO2 levels.
- Ventilation sized according to 800 ppm CO2 target level in occupied spaces, based on ambient CO2 level up to 400 ppm.

## **Building Engineering Systems**

#### Electrical includes

75% Plug Load Control
Natural Gas Back-up Generator
Fully Addressable Lighting System

#### Plumbing & Fire Protection *includes*

Typical fixture types provided in schools, reviewed by and coordinated with Facilities

Fire Pump (until Flow Test complete)
Chip tanks in Science rooms

#### Sustainability includes

All aspects of the proposed design were tested in the preliminary energy model that was presented at prior meetings, achieving a pEUI of 25.



# Estimating Process, Schedule, and Cash Flow Updates





### Final Feasibility Study Cost Estimate

24-Jun-21

				24-Jun-21	20-Jul-21	16-Sep-21	
District		Concord	Concord		Concord	Concord	
School Name	(	Concord MS	Concord MS		Concord MS	Concord MS	
Construction Type		New	New		New	New	
Enrollment		700	700		700	700	
GSF		142,995	145,647		143,660	143,510	
Assumed Start of Construction		March 2023	March 2023		March 2023	May 2023	
OPM		Hill International	Hill International		Hill International	Hill International	
Designer		SMMA	SMMA		SMMA	SMMA	
Cost Estimator		Based on AM Fogerty	Based on AM Fog	erty	Based on AM Fogerty	Based on AM Fogerty	
Gross SF		142,995		145,647	143,660	143,510	
Cost / SF		\$ 348.00	\$	348.00	\$ 348.00	\$ 348.00	
Construction		\$ 49,762,260.00	\$ 50,6	685,156.00	\$ 49,993,680.00	\$ 49,941,480.00	
Demolition / Hazmat		\$ 1,500,000.00	\$ 1,5	500,000.00	\$ 1,500,000.00	\$ 1,500,000.00	
Site Cost		\$ 7,500,000.00	\$ 7,5	500,000.00	\$ 7,500,000.00	\$ 7,500,000.00	
	TOTAL DIRECT	\$ 58,762,260.00	\$ 59,6	685,156.00	\$ 58,993,680.00	\$ 58,941,480.00	
Total Mark-ups		\$ 21,217,016	\$ 2	21,550,242	\$ 21,300,574	\$ 22,024,534	
Design Contingency	12.00%	\$ 7,051,471.20	\$ 7,:	162,218.72	\$ 7,079,241.60	\$ 7,072,977.60	
Escalation	8% or 9%	\$ 5,265,098.50	\$ 5,3	347,789.98	\$ 5,285,833.73	\$ 5,941,301.18	
GC	5.00%	\$ 3,553,941.48	\$ 3,6	609,758.23	\$ 3,567,937.77	\$ 3,597,787.94	
GR	2.50%	\$ 1,865,819.28	\$ 1,8	895,123.07	\$ 1,873,167.33	\$ 1,888,838.67	
Permits (waived)	0.00%						
P&P Bond	2.00%	\$ 1,529,971.81	\$ 1,5	554,000.92	\$ 1,535,997.21	\$ 1,548,847.71	
Profit	2.50%	\$ 1,950,714.06	\$ 1,9	981,351.17	\$ 1,958,396.44	\$ 1,974,780.83	
TOTAL	CONSTRUCTION	\$ 79,979,276.33	\$ 81,2	235,398.10	\$ 80,294,254.07	\$ 80,966,013.93	
CONSTRUCTION COS	ST PER STUDENT	\$114,256.11	L \$	116,050.57	\$114,706.08	\$115,665.73	
CONSTRUCTION COST PER SF		\$559.32			\$558.92		
	PROJECT COST	\$99,974,095.41	\$101,	544,247.62	\$100,367,817.59	\$101,207,517.41	
			Gym & Au	ditorium		Cost Escalation	
		Education Plan	Upsi		GSF Refinement	Update	

#### Factors

16-Sep-21

- Building Gross Square Footage (GSF)
- Time
- Committee charge to maintain \$100M Total Project Budget

#### Next Steps

Schematic Design
 Estimate and Value
 Management (Typ.)



### Schematic Design Estimating Process

#### Schematic Design Package – Friday, October 8th

SMMA delivers plans, specs, and narratives that define the current CMS Project Scope

#### Estimating & Reconciliation Process – 4 weeks (October 11<sup>th</sup> – Nov 4<sup>th</sup>)

- Two Professional Estimators PM&C and A M Fogarty (no subcontractors)
- Plan/spec review and Value Management (VM) Log finalization
- Estimates due Wednesday, October 27th
- OPM and Design Team review Oct 27-28
- Reconciliation Meeting Monday, November 1<sup>st</sup>

#### CMSBC – Friday, November 5th

- Review Reconciled Estimates / Project Cost
- Discuss Value Management (VM) Recommendation
- Vote VM Recommendation

#### CMSBC – Friday, November 12th

Vote to approve Schematic Design Scope and Budget



## Schematic Design Estimate Reconciliation Process

SAMPLE Snapshot

SCHEMATIC DESIGN COST ESTIMATE - RECONCILED								
6/11/2	221	86,130. sf		86,130. sf		86,130. sf		International
		RECONCILED	RECONCILED VALUE		PM & C, dated 6/11/2021		Ellana, dated 6/11/2021	
	Program Area		Cost/SF		Cost/SF		Cost/SF	PM&C - Ellana
NEW BUILDING		\$86,130 SF		86,130	SF	86,130 SF		
Α	Substructure							\$271,326
A10	Foundations							
	A1010 Standard Foundations	\$1,310,012	\$15.21 /sf	\$1,310,012	\$15.21 /sf	\$1,142,373	\$13.26 /sf	\$167,639
	A1020 Special Foundations	\$1,117,000	\$12.97 /sf	\$1,117,000	\$12.97 /sf	\$1,112,050	\$12.91 /sf	\$4,950
	A1030 Lowest Floor Construction	\$1,607,353	\$18.66 /sf	\$1,607,353	\$18.66 /sf	\$1,508,616	\$17.52 /sf	\$98,737
В	Shell							\$628,253
B10	Superstructure							
	B1010 Floor Construction	\$2,936,269	\$34.09 /sf	\$2,936,269	\$34.09 /sf	\$2,479,134	\$28.78 /sf	\$457,135
	B1020 Roof Construction	\$2,772,672	\$32.19 /sf	\$2,772,672	\$32.19 /sf	\$3,084,272	\$35.81 /sf	(\$311,600)
B20	Exterior Enclosure							
	B2010 Exterior Walls	\$7,640,691	\$88.71 /sf	\$7,640,691	\$88.71 /sf	\$6,944,733	\$80.63 /sf	\$695,958
	B2020 Exterior Windows	\$2,127,555	\$24.70 /sf	\$2,127,555	\$24.70 /sf	\$2,382,845	\$27.67 /sf	(\$255,290)
	B2030 Exterior Doors	\$237,076	\$2.75 /sf	\$237,076	\$2.75 /sf	\$268,250	\$3.11 /sf	(\$31,174)
B30	Roofing							
	B3010 Roof Coverings	\$3,107,200	\$36.08 /sf	\$3,107,200	\$36.08 /sf	\$3,044,976	\$35.35 /sf	\$62,224
	B3020 Roof Openings	\$11,000	\$0.13 /sf	\$11,000	\$0.13 /sf	\$0	\$0.00 /sf	\$11,000



### Schematic Design Value Management Process

Reconciled Estimate + VM = \$100M Total Project Budget

#### Example Scenario 1 – Under Budget

- \$95M + Add/Change Value Management Scope = \$100M
- \$95M + No Value Management Taken = \$95M

#### Example Scenario 2 – Over Budget

- \$105M + Deduct/Change Value Management Scope = \$100M
- \$105M + No Value Management Taken = \$105M



## Furniture, Fixtures, Equip. & Technology Budgets

#### Furniture, Fixtures, and Equipment

Design team uses Ed Plan and information gathered in Programming Meetings to develop first pass with Furniture Consultant.

List of furniture items and types reviewed with the School Department to confirm what they like and dislike (ie casters), experience with different furniture types, what have they recently ordered and plan on retaining if anything.

Budget and list are updated to be included in Project Budget (NOT in construction cost).

Current Budget Estimate: \$1,307,320.00

#### **Technology**

Design team uses Ed Plan and information gathered in Programming Meetings to develop first pass with Technology Consultant.

List of typical technology items is developed and reviewed with the School Department (including IT department) for input.


Budget and list are updated to be included in Project Budget (NOT in construction cost).

Current Budget Estimate: \$1,260,050.00




### Schedule

#### PHASE 1 - NEW SCHOOL DESIGN & CONSTRUCTION



#### PHASE 2 - SANBORN DEMO & NEW FIELDS



### **Cash Flow Update**

September 30, 2021

### Concord Middle School Estimated Project Cash Flow Thru SD Phase

		Month	ОРМ	Designer & Consultants	Commissioning Agent, FF&E & Misc.	Construction	Contingency	Estimated Expenditures	Actual Expenditures	Estimated Cumulative Expenditures	Actual Cumulative Expenditures
Feasibility Study	1	Oct-19	\$38,290					\$38,290	\$25,110	\$38,290	\$25,110
	2	Nov-19	\$20,550					\$20,550	\$34,595	\$58,840	\$59,705
	3	Dec-19	\$18,790					\$18,790	\$20,660	\$77,630	\$80,365
	4	Jan-20	\$18,790	\$75,645				\$94,435	\$88,210	\$172,065	\$168,575
	5	Feb-20	\$18,790	\$151,290				\$170,080	\$167,735	\$342,145	\$336,310
	6	Mar-20	\$24,070	\$161,376				\$185,446	\$101,535	\$527,591	\$437,845
_	7	Apr-20	\$22,670	\$105,903				\$128,573	\$110,125	\$656,164	\$547,970
	8	May-20	\$21,590	\$106,361				\$127,951	\$100,465	\$784,115	\$648,435
	9	Jun-20	\$21,590	\$96,275				\$117,865	\$73,474	\$901,980	\$721,909
	10	Jul-20	\$22,290	\$96,275				\$118,565	\$15,520	\$1,020,545	\$737,429
Pause	11	Aug-20	\$24,430	\$69,318				\$93,748	\$3,785	\$1,114,293	\$741,214
	12	Sep-20	\$53,450	\$26,957				\$80,407	\$720	\$1,194,700	\$741,934
	13	Oct-20						\$0	\$2,590	\$1,194,700	\$744,524
	14	Nov-20						\$0	\$0	\$1,194,700	\$744,524
₹	15	Dec-20						\$0	\$16,798	\$1,194,700	\$761,322
<u></u>	16	Jan-21						\$0	\$0	\$1,194,700	\$761,322
g è	17	Feb-21						\$0	\$0	\$1,194,700	\$761,322
ar s	18	Mar-21						\$0	\$0	\$1,194,700	\$761,322
est	19	Apr-21						\$0	\$0	\$1,194,700	\$761,322
OZ.	20	May-21						\$0	\$0	\$1,194,700	\$761,322
Schematic Design	21	Jun-21						\$0	\$2,400	\$1,194,700	\$763,722
	22	Jul-21						\$0	\$69,318	\$1,194,700	\$833,040
	23	Aug-21						\$0	\$69,318	\$1,194,700	\$902,358
	24	Sep-21						\$0	\$69,318	\$1,194,700	\$971,676
	25	Oct-21						\$0	\$0	\$1,194,700	
	26	Nov-21						\$0	\$0	\$1,194,700	
	27	Dec-21						\$0	\$0	\$1,194,700	
		Subtotal for FS/ SD	\$305,300	\$889,400	\$0			\$1,194,700			

#### Summary


- Current Commitments@ \$1,194,700
- \$971,676 spent through
   Sept 30, 2021
- \$223,024 SD Phase billings projected to be spent through Dec 2021
- \$305,300 uncommitted funds remain (from \$1.5M initial approved funding)



## **Cash Flow Update**



Town of Concord
Concord Middle School
Estimated Project Cash Flow Graph







# Thank you!

### more information:

https://www.cmsbuildingproject.org/

#### contact us at:

msbc@concordps.org

### follow us on:

Instagram: @cmsbcinconcord Twitter: @CMSBCinConcord

Facebook: CMS Building Committee (@cmsbcinconcord)



